5. WATER SERVICES INFRASTRUCTURE PROFILE

5.1 Existing water services infrastructure

ZDM has done extensive work on the development of a database that will serve as an asset register, but also to be used as the basis for the development of an asset management system and to capture asset related information electronically for ongoing use. The system has been named 'MANZI' and access can be gained on the ZDM website at <u>www.zululand.org.za</u> once the user has been issued with a username and password.

Table 5.1(a) below provides a brief overview of the schemes in the district that have been captured on the MANZI system and a summary of the infrastructure under consideration, as well as a rough estimate of the value of assets. These figures will be refined over time once the asset management system has been rolled out.

SUMMARY DATA	LOS	TOTAL
	Above RDP - Urban	14
Number of Cohemon	Above RDP - Rural	45
Number of Schemes	RDP	85
	Rudimentary	135
	TOTAL SCHEMES	279

Table 5.1(a): Summary of schemes in the district

Figures 5.1 (a), (b) and (c) and Table 5.1 (b) below show examples of infrastructure data that is currently available on the GIS system and also on MANZI. Although many gaps still exist in the infrastructure information ZDM is working on getting all information gaps systematically updated.

GROUP	COMPONENTS	TOTAL
Pipelinee	Bulk	905.6 km
ripelines	Reticulation	4,205.7 km
	Bulk Metering Points	58
	Meters	548
	Hand pumps	18
	Pumps	118
	Pump Stations	72
	Valves	7 944
	Electrical Connections	85
Installations	Abstractions / Sources	468
	JoJo Tanks	172
	Storage Reservoirs	644
	Treatment Plants/Packages	51
	Communal Standpipes	4 155
	Break-Pressure Tanks	169
	Yard Connections	21 198
	Water Offices	35
	Civil	R 176 869 818
Penlacement Value	Mechanical	R 51 655 500
	Electrical	R 20 449 000
	Telemetry	R 1 090 000

Table 5.1 (b): Summary of infrastructure components available on MANZI system



WATER INFRASTRUCTURE
Status Quo
2011
Legend SchemeComp_MASTER_Feb2011 Installati Score / Abstraction Pump Station Storage - Res Storage - Res WWW Treatment SchemePipes_MASTER_Feb2011 SupplyType Source Rising Main Bulk Supply Reticulation ZDM_Settlements_MASTER_Feb2011 RDP and Above Rudimentary Not Served
W S 0 2.5 5 10 km File: ECA WSDP 2010 - RWSS A3 mxd
ZULULAND
DISTRICT MUNICIPALITY

Figure 5.1 (b): Existing bulk infrastructure in the Ulundi-Mabedlane water scheme



Figure 5.1 (c): Existing reticulation networks in the Ulundi-Mabedlane scheme



The asset data in the MANZI system has been structured in a specific data hierarchy as indicated below:



Different asset groups have been identified for water and sanitation infrastructure and these could be either listed as installations, nodes or components. Asset data forms have been developed for each asset group and this is used to capture asset information in the database. The asset data forms provide an overview of the type of information that is available on each asset group. Examples of such asset groups are:

- Water treatment works
- Sewage works
- Pump stations
- Pipelines
- Reservoirs
- Meters
- Valves
- Electrical equipment, etc

The Nkonjeni Regional scheme is again used as an example to illustrate the data hierarchy that has been used. Inside the Nkonjeni Regional scheme footprint there currently exists a number of schemes, varying from RDP to rudimentary schemes. Each of the schemes are allocated a scheme ID number by the system that is used to identify the scheme in all reporting that is used and to link different assets to the scheme. One of the schemes within this footprint is the Ulundi-Mabedlane scheme and the information captured at "scheme" level is shown in Figure 5.1 (d) below:

SchemelD	S	icheme	Number					
	325	- on lonne						
Scheme Name								
Scheme Name								
Ulundi - Mac	bealane							
Population	Population S	erved	Level of Service			No of equipped work shops	No of paulooi	
13431	1	16094	Above RDP		¥	2	2	
Rural?								
Comments								
Sanitation L	OS: House c	onnec	tions 🔽			Form id: Uld1		1
San Served	8453	3						1
- · · · ·			1.11*				Scheme V	Working
Regional Sc	heme Consul	Itant:	Alliance	*				
Scheme Typ	be:		Water	*				
Class:		[*				
Schem	e Installations	;	#					

Figure 5.1 (d): Ulundi-Mabedlane scheme: information captured at "scheme" level

The Ulundi water treatment works is one of the installations on this particular scheme and the asset data form captured at "installation" level is shown below in Figure 5.1 (e):

rigure 5.1 (e). Ulundi water treatment works: information captured at installation lie	Figure 5.1	1 (e): Ulundi water treatm	ent works: informatior	n captured at	"installation"	' level
--	------------	----------------------------	------------------------	---------------	----------------	---------

InstallID		Schemel	Install_TypeID			Elevation		
	2359	3	25 Treatment		*			543
Latitude		L	ongitude		Cor	nstruction Date	Lifespan (Years)	
	-2	8.28175		31.339764		1985/01/02		40
Schematic No		Instal	ation Nodes	ABC: 2359				

Within the Ulundi water treatment works a number of nodes are listed, for example the raw water storage, sedimentation tanks, clarification process, sand filters, etc. The clarification process is used as an example in this case and the asset data form captured at "node" level is shown in Figure 5.1 (f) below:

Figure 5.1 (f): Ulundi water treatment works: clarification process: information captured at "node" level

Noc	lelD	Install[D Noc	le_TypeID	Elev	ation		
	2011	1	2359 Trea	atment (Clarification)	~		0	
Lati	tude		Longitud	le 🛛	Construc	ction Date	Lifespan (Y	'ears)
					10	000/01/01		0
Sch	ematic No				0		-	
Ĩ					Node (Component	s	
	Ngana ang ang ang ang ang ang ang ang ang				1055		- 64	
1	PhotoID	N	lode ID	Image Name		Date		
		1222	201	1 \Images\Ulundi WT	W 07.jpg			
	Caption			1		222	ALC: NO	
	Clarification			L		- contraction	A CAR	
				Conception of the second	and the			ALL AND A
						S	ALL DE L	
	1			Mar I I	and with			
		6 0	1	NK44				
	"+" ""	34		NR. A.				
			1	A RAN				
							1	
					KLE			
				- Lut				
Re	cord: M 1 of 1		H HO	No Filter Sear	ch			
Inc				Action men Sean	en l			

The different nodes within the Ulundi water treatment works comprise of a number of components. The clear water pump station is such a node that comprises of various components such as the high lift pumps, electrical equipment, etc. The asset data form captured for the clear water pump station at "component" level is shown in Figure 5.1 (g) below:

Figure 5.1 (g): Ulundi water treatment works: clear water pump station: information
captured at "component" level

	pID	Comp ID C	om_TypeID Pun	np Function	Pump Make	
	~%	203 5024	7 Rav	v water		~
Pum	р Туре	Pump	Duty (I/s)			
Unk	nown	×				
Brief	description of	controls				
Insta	all Date Lifes	pan (Yrs) Schemati	c No			
₩Na	ime? #Na	me? #Name?	1			
Con	nponent Pump	Drive				
	DrivelD	Pump ID	Drive Type		Fuel Tank Capacity (I)	
	1	918 1	203 Electricity	~	1	(
	Drive Kw rati	ng	Drive Speed (rp	m) Power Factor	Starting	_
		55	14	80	0	~
	Average ope	rating h/day 0	Install Date L #Name? #	ifespan (Yrs) Name?		
Re	cord: 🛛 📢 1	of 1 🕨 🕨 🕫	K No Filter	Search		
Con	nponent Photo					
	PhotoID	Comp ID	Image Nam	e	Date	
	THORONO	919 5	024 \Images\Ul	undi WTW 14.jpg		
	Caption					
	Final water p	ump				
	" + "	(8)	1			1
				and the second s	A DECEMBER OF A	

Schematic diagrams are also compiled for each scheme and basically summarises the main installations and nodes that make up the scheme. The diagram also shows how the installations and nodes are connected to make up the scheme and the direction of flow of the water or sewage. The schematic diagram also forms the basis for the development of a water balance and telemetry installation for the scheme. The Frischgewaagd scheme is used as an example and the schematic diagram is attached herewith in Figure 5.1 (h) below:



5.2 Asset management assessment

As mentioned above ZDM is well advanced with the development of MANZI, the ZDM asset management system. The system currently comprises mostly asset data and work is being done to develop operational and maintenance procedures for the assets, which will guide the activities for the ongoing upkeep of asset conditions. Assessments have already been done on certain issues related to asset management and further work needs to be done on other issues, as summarised below:

- <u>Human resources</u> The ZDM Section 78 investigation was finalised in 2007 and identified the most appropriate water services provider arrangement for the ongoing O&M of water services infrastructure in the district. Current staff organograms were compiled and compared with the minimum required staff resources needed to perform the O&M duties adequately. Shortages in staff numbers were identified and are being addressed over time within the ZDM financial means. Training of existing staff was also identified as a crucial element to ensure highly efficient personnel and this is being addressed annually as part of the ZDM Skills Development Plan. Certain functions have also been indentified that cannot cost effectively be developed in-house and will rather be contracted in externally.
- <u>Materials, tools & equipment, transport</u> The Section 78 investigation has also identified shortcomings in this regard and has listed vehicles and equipment to be purchased in order to have fully functional O&M teams. The need for additional stores has also been identified throughout the district and these are progressively being addressed with the available funding.
- <u>Budget</u> The Section 78 investigation has identified the funding requirements at present and in the future to adequately operate and maintain existing assets and new assets to be added over time. This information guides the preparation of the annual O&M budget, although available financial resources are not sufficient.
- <u>Asset information</u> The locality information on assets is very good and particularly the water assets are viewed to be more than 80% covered. Sewerage information is still lacking but is being addressed. Asset information that also still needs further work includes as-built information, design reports, operating manuals, safety plans, etc. Assessments were also done on asset conditions to determine a brief overview of the status of assets and start identifying where urgent work needs to be done. Photographs were taken of each asset visited and have been included into the MANZI system.
- <u>Risk management</u> ZDM realises that available resources will never really be sufficient to address all
 needs at once and therefore work has started on the development of a risk based approach to asset
 management. This model will consider the risk of failure of an asset, the consequence of such a failure
 and the probability of a failure occurring. This will all be compared to ensure that resources are applied
 where really needed most.
- <u>Reporting</u> The ZDM WSP reporting system will feed back valuable information to management regarding O&M activities and asset performance. This information will be used to adjust asset management priorities if needed and also track the efficiency of asset management projects that are being implemented.

5.3 Schemes to be transferred

All schemes and related staff that were identified to be transferred from DWAF and Department of Works to ZDM have been concluded. There are other schemes in the district still being operated by National Department of Works, e.g water services at prisons, but no formal or informal request have yet been entered into for the transfer of these schemes.

5.4 Schemes to be rehabilitated

There are currently a number of investigations underway to determine the refurbishment requirements of water services infrastructure in the district. The refurbishment requirements at bulk plants are receiving first priority since it is perceived that the most urgent interventions are required at these assets. Investigations are also being commissioned to determine the condition of urban infrastructure and the refurbishment needs in the towns. Whilst new infrastructure has been rolled out in the rural areas to previously neglected communities, the infrastructure in towns have received very little attention and funding since 1994 and it can be expected that most of the refurbishment requirements will be in these areas. The above mentioned investigations have not yet been fully completed and the results will be included once available.

Assessment of the bulk water and sewage works:

During June 2009 consultants were appointed to assess the Water and Waste Water Works in Zululand District Municipality. The assessments included recommendations and cost estimates to refurbish and/or upgrade these works in the short term and medium to long term. These assessments also recommended emergency interventions.

This Technical report was compiled to secure funding for the emergency interventions, short term refurbishment and medium to long term upgrading.

Emergency interventions are needed where work is needed to attend to fatal problem areas, such as settlements consuming raw untreated water, sewer water spilling directly into rivers and structures that is almost collapsing. Short term refurbishment (not critical work) is needed to refurbish and upgrade the existing works in order to meet the current demands and also to enable the works to function at its design capacity. These short term refurbishments were prioritised using criteria such as cost per capita and current demand versus current capacity.

Medium to long term upgrading (not critical work) is needed to upgrade the existing works in order to meet the future demands. These long term refurbishments were prioritised using criteria such as cost per capita and future demand versus the capacity after short term refurbishment. Some of these works will become redundant in future (As they will be incorporated into larger regional schemes). This was also taken into account.

		Current	Pogional Area	Local
14	lasta Watar Trastmont Warks	Delivery	Regional Area	Municipality
Waste Water Treatment Works		ML/d		
1	Frischgewaagd WWTW	0.08	Sim West	eDumbe
2	Paulpieterburg WWTW	0.30	Sim West	eDumbe
3	Vryheid Town WWTW	9.00	Hlahlindlela	Abaqulusi
4	eMondlo WWTW	2.40	Hlahlindlela	Abaqulusi
5	Nkongolwane WWTW	0.25	Coronation	Abaqulusi
6	Alpha Mine WWTW	0.00	Khambi	Abaqulusi
7	Hlobane WWTW	0.35	Coronation	Abaqulusi
8	Coronation WWTW	1.00	Coronation	Abaqulusi
9	Itshelejuba Hospital WWTW	0.09	Sim Central	uPongola
10	Pongola Town WWTW	2.50	Sim East	uPongola
11	Thulasizwe Hospital WWTW	0.03	Usuthu	Nongoma
12	Holinyoka/Nongoma WWTW	1.80	Usuthu	Nongoma
13	Ceza WWTW	0.14	Usuthu	Nongoma
14	James Nxumalo WWTW	0.08	Nkonjeni	Ulundi
15	Nkonjeni Hospital WWTW	0.20	Nkonjeni	Ulundi
16	St Francis Hospital WWTW	0.06	Nkonjeni	Ulundi
17	Ulundi Town WWTW	2.60	Nkonjeni	Ulundi
18	Enyathi WWTW	0.00	Coronation	Abaqulusi

Table 5.4 (a): The list of Waste Water Treatment works that were assessed

Table 5.4 (b): The list of Water Treatment works that were assessed

		Current	Regional Area	Local
	Water Treatment Works	Delivery		Municipality
		ML/d		
1	Frischgewaagd WTW	2	Sim West	eDumbe
2	eDumbe WTW (Paulpietersburg)	3	Sim West	eDumbe
3	Ophuzane WTW	0.5	Sim West	eDumbe
4	Tholakele WTW	0.5	Sim West	eDumbe
5	Klipfontein WTW	10	Hlahlindlela	Abaqulusi
6	Bloemveld WTW	5	Hlahlindlela	Abaqulusi
7	Mondlo WTW	9	Hlahlindlela	Abaqulusi
8	Mvuzini WTW	0.5	Hlahlindlela	Abaqulusi
9	Purim WTW	0.24	Hlahlindlela	Abaqulusi
10	Hlobane WTW	2	Coronation	Abaqulusi
11	Louwsburg WTW	0.72	Coronation	Abaqulusi

		Current	Pegional Area	Local
	Water Treatment Works	Delivery	Regional Alea	Municipality
		ML/d	_	-
12	Coronation WTW	0.4	Coronation	Abaqulusi
13	Khambi WTW	0.2	Khambi	Abaqulusi
14	Mountain View WTW	0.05	Khambi	Abaqulusi
15	Belgrade WTW	1.1	Sim Central	uPongola
16	Msibi WTW	0.03	Sim Central	uPongola
17	Khiphunyawo WTW	0.37	Sim Central	uPongola
18	Nkosentsha WTW	0.13	Sim Central	uPongola
19	Spekboom WTW	1.8	Sim East	uPongola
20	Pongola WTW	6.3	Sim East	uPongola
21	Osingisingini WTW	0.04	Usuthu	Nongoma
22	Thulasizwe Hospital WTW	0.2	Usuthu	Nongoma
23	Vuna WTW	4.2	Usuthu	Nongoma
24	Ceza WTW	0.4	Usuthu	Nongoma
25	Khangela Palace WTW	0.01	Usuthu	Nongoma
26	Enyokeni Palace WTW	0.02	Usuthu	Nongoma
27	Ulundi WTW	18	Nkonjeni	Ulundi
28	Mpungamhlope WTW	0.63	Nkonjeni	Ulundi
29	Babanango WTW	0.33	Nkonjeni	Ulundi
30	Enyathi WTW		Coronation	Abaqulusi
31	Mandlakazi WTW		Mandlakazi	Nongoma
32	Sidinsi WTW		Mandlakazi	Nongoma
33	Kombusi WTW		Mandlakazi	Nongoma
34	Embile WTW		Usuthu	Nongoma
35	Masokaneni WTW		Nkonjeni	Ulundi
36	Nkonjeni Hospital WTW		Nkonjeni	Ulundi

Table 5.4 (b): The list of Water Treatment works that were assessed (continued)

The results of the assessments are shown in Tables 5.4 (c) & (d) below:

Table 5.4 (c): Assessment of Water Treatment works

Water Treatment Works		Current Estimate Delivery Emergency Work		Cost Estimate Short Term		Cost Estimate Long Term (Excludes short term)		
		ML/d	ex VAT and Prof fees		ex VAT and Prof fees		ex VAT and Prof fees	
1	Frischgewaagd WTW	2	R	-	R	1 040 000	R	45 000 000
2	eDumbe WTW	2	Б		Б	0 400 000	Р	20,000,000
2		3	R D	-	R D	2 490 000	R D	20 000 000
3		0.5	P			540 000	P	
4 5	Klipfontein WTW	10	R		R	8 870 000	R	4 415 000
6	Bloemveld WTW	5	R		R	3 640 000	R	5 200 000
7	Mondlo WTW	9	R	480 000	R	180 000	R	2 400 000
8	Myuzini WTW	0.5	R		R	-	R	-
9	Purim WTW	0.24	R	-	R	-	R	250 000
10	Hlobane WTW	2	R	450 000	R	1 590 000	R	-
11	Louwsburg WTW	0.72	R	320 000	R	2 500 000	R	_
12	Coronation WTW	0.4	R	850 000	R	1 140 000	R	22 000 000
13	Khambi WTW	0.2	R	-	R	-	R	150 000
14	Mountain View WTW	0.05	R	-	R	-	R	265 000
15	Belgrade WTW	1.1	R	226 000	R	95 300	R	12 500 000
16	Msibi WTW	0.03	R	74 000	R	2 055 000		
17	Khiphunyawo WTW	0.37	R	18 000	R	4 140 000		
18	Nkosentsha WTW	0.13	R	77 000	R	1 680 000		
19	Spekboom WTW	1.8	R	334 500	R	1 607 200		
20	Pongola WTW	6.3	R	215 000	R	110 200	R	20 000 000
21	Osingisingini WTW	0.04	R	14 000	R	672 000		
22	Thulasizwe Hospital WTW	0.2	R	16 100	R	42 000	R	800 000
23	Vuna WTW	4.2			R	323 500		
24	Ceza WTW	0.4	R	2 000	R	2 030 000		
25	Khangela Palace WTW	0.01	R	800	R	1 335 000		
26	Enyokeni Palace WTW	0.02	R	36 700	R	28 000		
27	Ulundi WTW	18			R	530 000		
28	Mpungamhlope WTW	0.63	R	17 600	R	35 000	R	20 000 000
29	Babanango WTW	0.33	R	3 400	R	2 335 000	R	-
30	Enyathi WTW	No assessments Scheduled						
31	Mandlakazi WTW	Assessment outstanding						
32	Sidinsi WTW	Assessment outstanding						
33	Kombusi WTW	Assessment outstanding						
34	Embile WTW	No assessments Scheduled						
35	Masokaneni WTW	No assessments Scheduled						
36	Nkonjeni Hospital WTW	No assessments Scheduled						
37	Usuthu WTW	0.00	0.00					100 000 000
			R	3 135 100	R	39 008 200	R	252 980 000

Waste Water Treatment Works		Current Delivery	Cost Estimate Emergency Work	Cost Estimate Short Term	Cost Estimate Long Term (Excludes short term)
		ML/d	ex VAT and Prof fees	ex VAT and Prof fees	ex VAT and Prof fees
1	Frischgewaagd WWTW	0.08	R 0	R 300 000	R 40 000 000
2	Paulpieterburg WWTW	0.30	R 550 000	R 1 800 000	R 0
3	Vryheid Town WWTW	9.00	R 0	R 0	R 0
4	eMondlo WWTW	2.40	R 725 000	R 3 630 000	R 5 500 000
5	Nkongolwane WWTW	0.25	R 0	R 0	R 990 000
6	Alpha Mine WWTW	0.00	R 0	R 300 000	R 0
7	Hlobane WWTW	0.35	R 900 000	R 3 150 000	R 450 000
8	Coronation WWTW	1.00	R 850 000	R 3 980 000	R 6 000 000
9	Itshelejuba Hospital WWTW	0.09		R 70 000	R 800 000
10	Pongola Town WWTW*	2.50	R 13 000	R 363 500	R 1 390 000
11	Thulasizwe Hospital WWTW	0.03		R 220 000	R 50 000
12	Holinyoka/Nongoma WWTW**	1.80		R 1 719 753	R 4 310 000
13	Ceza WWTW	0.14		R 660 000	R 2 000 000
14	James Nxumalo WWTW	0.08		R 270 000	R 890 000
15	Nkonjeni Hospital WWTW	0.20		R 70 000	R 1 770 000
16	St Francis Hospital WWTW	0.06		R 75 000	R 840 000
17	Ulundi Town WWTW**	2.70		R 600 000	R 2 900 000
18	Enyathi WWTW	0.00	No assessments Scheduled		
	Total		R 3 038 000	R 17 208 253	R 67 890 000

Table 5.4 (d): Assessment of Waste Water Treatment works





5.5 New infrastructure to be built

Water infrastructure:

During 2004 the ZDM started a comprehensive water master planning exercise to determine the most appropriate methods of providing previously neglected communities with water services. In all cases the main drivers were to obtain the technical solution that will not necessarily be the lowest in terms of capital requirements to implement, but rather that will provide a sustainable service throughout the year (sustainable water source) at the lowest possible water tariff (R/kl). The first step was to identify sustainable water sources in the district that could be used to provide water supply even during extreme drought situations and then to determine the most cost efficient way of supplying communities from these sources. The planning methodology that was used can be summarised as follows:

- Identify logical supply footprints
- Identify all possible options for supplying water to supply footprints
- Determine the capital and operational costs associated with each option
- Evaluate each option
- Decide on most appropriate solution

From the above planning process the entire district was covered with 10 back to back regional schemes, which are listed below and indicated on Figure 5.5 (a) attached herewith:

- Nkonjeni regional scheme
- Usuthu regional scheme
- Mandlakazi regional scheme
- Mkhuze regional scheme
- Simdlangentsha East regional scheme
- Simdlangentsha West regional scheme
- Simdlangentsha Central regional scheme
- Coronation regional scheme
- Khambi regional scheme
- Hlahlindlela regional scheme

Also indicated herewith on Figure 5.5 (b) is the planned future bulk infrastructure that was identified from the above planning process.

Sanitation infrastructure:

Further planning work is still required in the urban areas to confirm the suitability of the bulk infrastructure, especially with regards to increased pressures on this infrastructure due to an increasing urbanisation trend that has been occurring and also to allow for future growth in population.

Sanitation infrastructure being provided in rural areas (previously unserved communities) is limited to household VIP toilets. The units are being implemented on the back of the water infrastructure roll-out plan.

Estimated costs:

Table 5.5 (a) below summarises the estimated costs to provide sufficient water services infrastructure to all households in future:

REGIONAL SCHEME	WATER		SANITATION			
Nkonjeni	R	369 105 360	R	75 294 000		
Usuthu	R	1 321 889 255	R	141 126 000		
Mandlakhazi	R	515 450 250	R	53 742 000		
Mkhuze	R	17 572 455	R	3 120 000		
Simdl East	R	40 000 000	R	17 688 000		
Simdl Central	R	80 036 964	R	16 638 000		
Simdl West	R	172 901 728	R	1 752 000		
Khambi	R	100 029 335	R	10 518 000		
Coronation (Enyathi)	R	185 621 339	R	10 824 000		
eMondlo	R	289 215 884	R	44 052 000		
Rural Sanitation	North		R	3 500 000		
Plants	South		R	3 500 000		
TOTALS	R	3 091 822 570	R	381 754 000		

Table 5.5 (a): Cost of new infrastructure to be built





